

EDUCATION CASE STUDY CATON COURT, LANCASTER.



Project Summary

This was a scheduled 20 week contract where we had supervision on site at all times to ensure we planned and coordinated all labour in to all the areas as soon as they became available.

Application methods were initial coats to ceiling & walls applied by airless spray (Masking up all the non-painted surfaces prior to spray & de-masking & disposing of all waste at the end of each shift.)

We sprayed woodwork with initial coats to prior to fixing on site which cut down some labour time on site which helped with the tight timescales to achieve the completion dates.

Painting to ceilings, walls, woodwork, window boards, architraves, skirts, door frames, boxings, MDF facings, concrete floors using epoxy paints. Painting was also completed to feature walls including setting out and masking prior to painting & de-masking on completion and finally painting to Sky lounge steel columns with Sherwin Williams C137 V2 top coat.

We masked up all non-painted surfaces and applied the final coats on site after the furniture was fitted, to minimise any damage by others at the end of the project and de-masked on completion.

We also supplied a small aftercare gang at the end to pick up on any remedial works caused by others outside of this.

We utilised up to 25 decorators at the jobs peak in August to ensure the clients deadlines were met to allow the Students to occupy the building in September term, this included working long hours & weekends under difficult conditions with other trades.

Key Facts

Project Name	Caton Court, Lancaster
Client	Eric Wright Construction
Service	Painting and Decorating, including Spraying
Length of Contract	9 months

Carlisle Office

Head Office, Brunthill Road, Kingstown Industrial Estate, Carlisle CA3 0EH T: 01228 404 114

Manchester Office

Unit 6, Westlink Business Park, Guide Street, Salford M50 1EW T: 0161 925 0412